

GENERAL NOTES:

- 1. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROVIDING ALL LABOR, MATERIALS, EQUIPMENT, AND SUPERVISION NECESSARY FOR FURNISHING AND INSTALLING NEW ROOFING IN
- CONFORMANCE WITH THE DETAILS AS SHOWN. 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VISITING THE SITE AND PERFORMING ANY AND ALL REQUIRED MEASUREMENTS USED IN PREPARATION OF BIDDING DOCUMENTS. ALL DIMENSIONS ARE APPROXIMATE. PARAPET WALLS NOT INCLUDED IN DIMENSIONS.
- IT WILL BE THE CONTRACTORS RESPONSIBILITY TO LOCATE ALL SITE UTILITIES. IF DAMAGE OCCURS TO ANY UTILITIES, IT MUST BE REPAIRED AT CONTRACTORS OWN EXPENSE.
- WORK AREAS SHALL BE ROPED OFF AROUND WORK SITES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR BLOCKING OFF AREAS AS REQUIRED. FURNISHING THE NECESSARY BARRICADES. SIGNS, ECT...ALL ENTRANCES SHALL REMAIN OPERATIONAL AT ALL TIMES UNLESS PRIOR PERMISSION HAS BEEN OBTAINED TO RESTRICT OTHER THAN EMERGENCY ACCESS.
- UPON FINAL CLEAN-UP. THE CONTRACTOR SHALL REMOVE ANY DEBRIS. RUBBISH. AND EXCESS MATERIAL FROM THE STATION. THE CONTRACTOR SHALL FOLLOW ALL APPLICABLE VAMC REGULATIONS, OSHA STANDARDS AND INTERIM LIFE SAFETY MEASURES.
- OWN EXPENSE.
- APPROVAL, PRIOR TO THE START OF ANY WORK. DEMOLISHED AREAS SHALL BE REPAIRED WITHIN 4 WORKING DAYS OF THEIR REMOVAL. THE CONTRACTOR SHALL BE RESPONSIBLE FOR A SCHEDULE ALLOWING A MINIMUM OF TEN (10) DAYS ADVANCE NOTICE OF THE PLANNED START OF WORK/CONSTRUCTION ACTIVITIES. THE CONTRACTOR WILL BE ALLOWED TO WORK AFTER POLICE WHEN WORKING AFTER HOURS.
- 11. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PROTECT THE ROOF FROM STORM DAMAGE DURING REMOVAL OF EXISTING ROOFING.
- SHALL ALSO BE REMOVED. ALL SCRAPE METAL SHALL REMAIN PROPERTY OF THE VAMC AND THE CONTRACTOR SHALL DISPOSE OF IT IN BUILDING 79.
- 14. ALL SCUPPERS AND DOWNSPOUTS SHALL BE REMOVED AND REPLACED WITH GALVANIZED METAL AND SHALL BE PRIMED AND PAINTED (TWO COATS) TO MATCH OTHER EXISTING BUILDINGS IN ADJACENT AREA. A CAST IRON CLEAN-OUT SHALL BE INSTALLED AT THE BASE OF ALL DOWNSPOUTS THAT CONNECT BELOW GROUND. (SEE DOWNSPOUT CLEAN-OUT DETAIL). THE CONTRACTOR SHALL MACHINE AUGER ALL UNDERGROUND STORM DRAINS A MIN. OF 60 FEET. BEFORE INSTALLING THE CAST IRON CLEAN-OUT
- ASPHALT GUTTER LINER ACCORDING TO THE BOX GUTTER DETAIL. ANY EXPOSED GUTTER SHALL BE PRIMED AND PAINTED (TWO COATS) TO MATCH THE COLOR OF THE GUTTER LINER.
- INSTALLED THE CONTRACTOR SHALL EXAMINE THE EXISTING DECKING TO MAKE SURE THAT THE DECKING IS SECURELY NAILED DOWN TO THE RAFTERS. IF ADDITIONAL NAILING IS NECESSARY IT WILL BE THE CONTRACTORS RESPONSIBILITY TO SECURE THE DECKING WITH #8 SINKER NAILS. THE FELT PAPER SHALL BE SECURED BY 1-1/4" BUTTON CAPPED NAILS MIN. WITH PLASTIC
- 17. 1-3/4" WHITE ALUMINUM DRIP EDGE SHALL BE USED ON GABLE ENDS. ALL FLASHING SHALL BE REPLACED WITH NEW STAINLESS STEEL FLASHING.
- 13. FLAT ROOF MEMBRANE SHALL CONSIST OF .060 MIL (K.E.E.) KETONE ETHYLENE ESTER FLEECED BACKED (WHITE) MEMBRANE OVER 5" MIN. POLYISOCYANURATE THAT IS MECHANICALLY FASTENED OR ADHERED WITH LOW RISING FOAM. THICKNESS MAY BE LESS ADJACENT TO DRAINS AND OVERFLOWS.
- 14. ALL PARAPET WALLS SHALL BE COMPLETELY COVERED WITH ROOFING MEMBRANE AND TERMINATED UNDER EXISTING CAP STONE. THE CONTRACTOR SHALL GRIND OUT AND TUCK POINT ALL
- 15. NEW 2' x 2' WALKWAY PADS SHALL BE INSTALLED. ALL PADS SHALL BE CONCRETE PADS WITH A RUBBER PAD UNDER LINER.
- 16. PRIME AND PAINT (TWO COATS) ALL VTR'S, NEW LADDERS, STAIRS, HANDRAILS, CONDUITS, ETC... WITH APPROVED SUBMITTED COLOR.
- 17. THE CONTRACTOR SHALL INCLUDE IN THEIR BID A BREAKDOWN OF THE COST PER SQUARE FOOT OF LABOR AND MATERIALS TO REPLACE ANY DAMAGED OR ROTTED DECKING OR EVE'S FOR A TOTAL OF A \$2500.00 ALLOWANCE. ANY AMOUNT OF THIS ALLOWANCE NOT USED SHALL BE CREDITED TO THE GOVERNMENT. ANY AMOUNT MORE THAN \$2500.00 SHALL BE APPROVED BY THE PROJECT ENGINEER. OVERHEAD AND PROFIT SHALL NOT BE INCLUDED.



DOWNSPOUT **CLEAN-OUT DETAIL**

BOX GUTTER DETAIL




LEGEND

= STONE COATED STEEL SHINGLES

= KETONE ETHYLENE ESTER FLEECE BACKED MEMBRANE (K.E.E.)

= DOWNSPOUT CLEAN-OUT LOCATION



= DOWNSPOUT WITH OUT CLEAN-OUT LOCATION

= VENT THROUGH ROOF (VTR)

Approved: Acting Medical Center Director Daniel Hendee, FACHE

Approved: Engineering Department Charles Applewhite

Approved: Medical Center Assoc. Director Approved: Project Director

ROOF DETAIL

610-12-182 REPLACE ROOF, B-122 Drawing Number MARION, IN 12-103M 3/28/2012 APPLEWHITE Z. MCDANIEL Dwg. 2 of 2

Project Title



VA FORM 08-6231, OCT 1978